

Webster & Nicholas Sewer Separation, Phase 1 Project



COMPLETED DATE:

- Q4 2015



COST AT COMPLETION:

- \$9.4 million



PROJECT LOCATION:

- In the Burt-Izard Basin, at 16th and Nicholas Streets and surrounding areas



The Webster and Nicholas Sewer Separation Phase 1 Project, which builds upon sewer separation already completed as part of the CSO Program, was accomplished in two parts.

The first part involved the construction of storm and sanitary sewer on Nicholas Street between 16th and 20th Streets. The project started with a connection to the west end of the storm and sanitary sewers constructed as part of the Nicholas Street Phase 1 (10th Street to 16th Street) Project. Construction involved full width removal and replacement of 16th Street north of Nicholas Street and Nicholas Street from 16th to 20th Street. New sidewalk and ramps were provided as part of this effort. The second part of the project included the construction of one block of sanitary sewer tunneled in place on 15th Street from Mike Fahey Street to California Street.

